

**APARNA PROPERTY MANAGEMENT SERVICES PVT. LTD.**

#802, Astral Heights, D.No: 6-3-352/2 & 3,
Road No 1, Banjara Hills, Hyderabad - 500034
CIN NO : U45201TG2007PTC054076
Phone : +91-40-23352068/72 Fax : + 91-40-23350329

**WORK ORDER**

To ALLIANCE SECURITY SYSTEMS
#301, Kaizen Imperial Heights, D.No.6 - 3 - 1219/7, Str no -,2,
Secunderabad-, Telangana, India

WO : APMS\WO\146\00057
Date : 26/03/2019
Project : Aparna Sarovar

PH : **Fax** :
Mobile : 9848124717 **PAN No** : ABZPV8661N
GSTIN : 36ABZPV8661N1Z6
Email :
Contact Person : Mr. V.Vijaya Bhaske

Ref Annual Maintenance charges for Solar fencing -1132 mtrs at Sarovar Site
Please Execute the under mentioned work subject to Terms & Conditions mentioned in this Order & overleaf. Please quote this Order No. in all your supply documents.

Scope of work: (Without original GST Invoice, material shall not be accepted at our stores)

- 1) You shall do the Periodical service to the product once in every 2 months in the first week (i.e 3 service calls per 6 months).
- 2) You shall attend the Six breakdown calls per year on free of cost basis and additional breakdown calls @ RS.1500/- extra per visit.
- 3) Service includes cleaning, applying of lubricants at control panel whenever applicable. Total fencing length - 1132 meters.
- 4) Cleaning of fence accessories and submitting the service report in detail to the concern authority and taking the acknowledgement for the service executed.
- 5) AMC Period : 01.04.2019 to 30.09.2019--06 Months.
- 6) Please refer Annexure- I for detailed description of the work along with checklist.

S No	Code	SAC	Item Description	UOM	Qty	Unit Rate	Tax Rate(%)			Amount
							SGST	CGST	IGST	
1	SI1061	998719	AMC for Solar fencing system For 1132 mtrs at Aparna Sarovar project. W.e.f. 01.04.2019 to 30.09.2019 (6 months) As per enclosed Annexure-1	MNT H	6.00	1833.33	9.00	9.00	0.00	10999.98
Payment : Quarterly after completion of the work along with previous month service reports certified by APMS In-charge				Sub - Total						10999.98
				SGST						990.00
				CGST						990.00
				IGST						0.00
Warranty : You shall maintain the system in 100% working condition				Grand Total						12979.98
				Rounded off To						12980.00

Value In Words : Rupees Twelve Thousands Nine Hundred Eighty Only

Material Delivery Address : Nallagandla village, Kanchagachibowli,
Gopanapally post, R R Dist,
HYDERABAD - 500 049

Contact : S. Vinay
Mobile No : 7337351734 / 040 67766070
stores-sarovar@apmspl.com
GSTIN : 36AAGCA3703R1ZE
Range Code : YNO701

Prepared By
26/3/19

Checked By
26/03/19

Authorized Signatory

Ref. No.: AD Per TOM Dated 25/3/19

Date

Activity

Non Comprehensive AMC for solar fencing

ANNEXURE –I

THIS ANNEXURE FORMS AN INTEGRAL PART OF OUR WO – APMS\WO\146\00057, Dt: 25.03.2019

Scope of Work:

- 1) Thorough check of the Power Generating Unit such as performance of the Solar PV Module, Input & Out voltages of the Battery, Input & Output voltages of the Control Panel, Alarm condition, Earthing System etc. Extending the repair works required if any.
- 2) Periodical service to the product once in every 2 months in the first week (i.e. 6 Service calls per year),
- 3) 6 breakdown calls per year shall be attended by you on free of cost and additional breakdown calls Rs.1500/- extra per visit.
- 4) Checking of the Fence condition includes identifying & repairing the damages if any.
- 5) Checking the earthing condition, checking the activation of siren any unauthorized tampering with the system.
- 6) Proposing for the accessories required, if any.
- 7) Submitting the Service Report in detail to the concerned authority and taking the Acknowledgement for the services executed .
- 8) Spares parts, if required shall be supplied by you on reasonable cost.

CHECK LIST FOR SERVICES AMC:

Central Control Panel System:

S.No.	Components	Servicing Process
1	Solar PV Module	Cleaning the panels properly and noting the output voltage
2	Control Unit	Checkup all the fasteners and clean and noting the input & output voltages
3	Alarm System	Check the performance, advice to replace, if the sound is not louder
4	Battery	Top-up the distilled water, clean the terminals, apply the gel to the terminals and fix tightly, noting the output voltage
5	DI Cables	Checkup the quality & replace, if needed
6	LDK	Check the fasteners, check the Arrestor replace the Arrestor if spoiled
7	Neon Tester	Cross check the functioning with DVM
8	Super Earth Kits	Check the efficiency with DVM (suggest to keep the Earth Kits in moisture condition)

Fence

S.No.	Components	Servicing Process
1	Insulators/accessories	Check the quality of all spares and replace the components whichever damaged
2	Fence Trimming	Keep the fence in tight condition by tightening the wire tighteners
3	Super Earth Kits	Keep the earth kits in moisture condition
4	Joint clamps	Tight the clamps firmly and replace the clamps whichever effected with rust
5	Warning Sign Boards	Keeping them intact ✓