

H. No 5-9-285/3, 2nd Floor, Rajiv Gandhi Nagar.

An ISO 9001:2008 & OHSAS 18001:2007 Certified Organization

TEST REPORT

CUSTOMER NAME & ADDRESS		TEST REPORT NO.	VCR - 1195 - 0519	
M/s. Aparna Property Management Services, Hyderabad.		REPORT ISSUE DATE	30" May 2019	
		REGISTRATION NO.	VEL/459A 11 th May 2019	
		REGISTRATION DATE		
		CUSTOMER REFERENCE		
SAMPLE DESCRIPTION	WTP water - Inlet	REFERENCE DATE	-	
		ANALYSIS STARTING DATE	13 th May 2019	
SAMPLE SITE	Aparna, Sarovar	ANALYSIS COMPLETION DATE	17th May 2019	
		STORAGE CONDITION	0-4°C	
		CONDITION UPON RECEIPT	Acceptable	
QUANTITY RECEIVED		1000 ml		
SAMPLE COLLECTED OR SUBMITTED		By client		

TEST RESULTS

S.NO.	PARAMETERS	UNITS	TEST METHOD	RESULTS	LIMITS
	& Chemical Parameters	-			1 1
Physical	pH		IS 3025 P-11	7.5	6.50 - 8.50
1		μs/cm	АРНА	627.0	Not Specified
2	Conductivity	Hazen	IS 3025 P-4	0.1	5
3	Colour	NTU	IS 3025 P-10	0.3	<1
4	Turbidity Table Discount Solids	mg/l	IS 3025 P-16	314.6	<500
5	Total Dissolved Solids Alkalinity to Phenolphthalein as CaCO ₃	mg/l	IS 3025 P-23	Nil	Not specified
6	Alkalinity to methyl orange as CaCO ₃	mg/l	IS 3025 P-23	71.3	<200
7		mg/l	IS 3025 P-21	205.1	<200
8	Total Hardness as CaCO ₃ Non carbonate Hardness as CaCO ₃	mg/l	IS 3025 P-21	133.8	Not specified
9		mg/l	IS 3025 P-40	54.3	<75
10	Calcium as Ca	mg/l	IS 3025 P-46	14.7	<30
11	Magnesium as Mg	mg/l	IS 3025 P-45	6.2	Not Specified
12	Sodium as Na	mg/l	IS 3025 P-45	1.3	Not Specified
13	Potassium as K	mg/l	IS 3025 P-53	0.2	<0.3
14	Iron as Fe	_	APHA	7.5	Not Specified
15	Silica as SiO ₂	mg/l	APHA	0.1	<1.0
16	Fluoride as F	mg/l	-	87.3	<250
17	Chlorides as Cl	mg/l	IS 3025 P-32	_	
18	Sulphates as SO ₄	mg/l	IS 3025 P-24	14.1	<200
19	Nitrates as NO ₃	mg/l	IS 3025 P-34	7.0	<45
20	Chlorine demand	mg/l	APHA	0.4	<10

Note: The result relates to sample tested only. Limits are given as per IS 10500-2012 dri specification.

Authorized Signatory