

H. No 5-9-285/3, 2nd Floor, Rajiv Gandhi Nagar,

An ISO 9001-2008 & OHSAS 18001-2007 Certified Organization

TEST REPORT

CUSTOMER NAME & ADDRESS		TEST REPORT NO.	VCR - 1318 - 0619	
M/s. Aparna Property Management Services, Hyderabad.		REPORT ISSUE DATE	28th June 2019	
		REGISTRATION NO.	VEL/594	
		REGISTRATION DATE	13th June 2019	
		CUSTOMER REFERENCE	**	
SAMPLE DESCRIPTION	WTP water - Outlet	REFERENCE DATE	**	
		ANALYSIS STARTING DATE	14 th June 2019	
SAMPLE SITE	Aparna, Sarovar	ANALYSIS COMPLETION DATE	20th June 2019	
		STORAGE CONDITION	0-4°C	
		CONDITION UPON RECEIPT	Acceptable	
QUANTITY RECEIVED		1000 ml		
SAMPLE COLLECTED OR SUBMITTED		By client		

TEST RESULTS

S.NO.	PARAMETERS	UNITS	TEST METHOD	RESULTS	LIMITS
Physica	& Chemical Parameters		7.0	797	
1	pH		IS 3025 P-11	7.0	6.50 - 8.50
2	Conductivity	μs/cm	APHA	234.6	Not Specified
3	Colour	Hazen	IS 3025 P-4	0.1	<5
4	Turbidity	NTU	IS 3025 P-10	0.2	<1
5	Total Dissolved Solids	mg/l	IS 3025 P-16	140.0	<500
6	Alkalinity to Phenolphthalein as CaCO ₃	mg/I	IS 3025 P-23	Nil	Not specified
7	Alkalinity to methyl orange as CaCO ₃	mg/l	IS 3025 P-23	41.8	<200
8	Total Hardness as CaCO ₃	mg/l	IS 3025 P-21	90,3	<200
9	Non carbonate Hardness as CaCO ₃	mg/l	IS 3025 P-21	48.5	Not specified
10	Calcium as Ca	mg/l	IS 3025 P-40	25.3	<75
11	Magnesium as Mg	mg/l	IS 3025 P-46	12.1	<30
12	Sodium as Na	mg/l	IS 3025 P-45	3.4	Not Specified
13	Potassium as K	mg/l	IS 3025 P-45	1.0	Not Specified
14	Iron as Fe	mg/l	IS 3025 P-53	0.1	<0.3
15	Silica as SiO ₂	mg/l	APHA	4.8	Not Specified
16	Fluoride as F	mg/l	АРНА	0.1	<1.0
17	Chlorides as Cl	mg/l	IS 3025 P-32	49.1	<250
18	Sulphates as SO ₄	mg/l	IS 3025 P-24	7.8	<200
19	Nitrates as NO ₃	mg/l	IS 3025 P-34	3.6	<45
20	Chlorine demand	mg/l	APHA	0.2	<1.0

Note: The result relates to sample tested only. Limits are given as per IS 10500-2012 drinking water specification.

Authorized Signatory