



APARNA SHELTERS PVT. LTD.
#802,Astral Heights, D.No: 6-3-352/2 & 3,
Road # 1, Banjara Hills, Hyderabad - 500034
Phone : +91-40-23352068/72 Fax : + 91-40-23350329



Ref No : ASPL_CONSV\402-EXT.SER\S02172\ASP\SCO\402\0018\A0 (FRESH)

Date : 23/11/2018

To :

SECURITY ALERT SYSTEMS - HYDERABAD,

H.No:9F, Phase-1

Janapriya Nagar, Miyapur,
Hyderabad.

Email :ravi@securityalertsystems.co.in

TIN NUMBER : 36712669740
PAN NUMBER : AUJPB4938M
GST NUMBER : 36AUJPB4938M1Z9

Project : EXT.SER - Lotus-Villas at Gundlapochampally,Hyderabad,

Subject : Supply, Installation, testing & Commissioning of CCTV Works @ Kanopy Lotus Villas

Area Allocated :

CCTV Works

Kind Attention : RAVIKUMAR. B Cell No.040-48507718 9989393850

Dear Sir,

With reference to the above subject, and subsequent discussions we had with you, we are pleased to place the Supply, Installation, testing & Commissioning of CCTV Works @ Kanopy Lotus Villas as per the specifications Terms and Conditions.

We are pleased to award this order to you to carry out the above works. The total order amount is Rs. 293877.00(Rupees Two Lakh Ninety Three Thousands Eight Hundred Seventy Seven Only) based on your offer referred above and our discussions.

As per the discussions, you shall execute above works to our fullest satisfaction on the critical project control parameters like quality, time schedule for completion of above works.

All terms & conditions as discussed are valid except for the under noted variations & stipulations.



APARNA SHELTERS PVT. LTD.
#802,Astral Heights, D.No: 6-3-352/2 & 3,
Road # 1, Banjara Hills, Hyderabad - 500034
Phone+91-40-23352068/72 Fax :+ 91-40-23350329



Annexure-1 (BOQ)

Project : 402-EXT.SER - EXT.SER - Lotus-Villas
 Contractor : S02172 - SECURITY ALERT SYSTEMS - HYDERABAD
 Subject : Supply, Installation, testing & Commissioning of CCTV Works @ Kanopy
 Ref. No : ASPL_CONS\J402-EXT.SER\S02172\ASP\SCO\402\0018\A0 (FRESH)
 IBMS & Security

S/n	Work Area	Description of Work	UOM	Quantity	Rate	Amount	WBS ID
-----	-----------	---------------------	-----	----------	------	--------	--------

CCTV & Access Control System Works

Supply and installation ,testing & commissioning of 2MP Our Door Bullet camera, Very focul type, 40Mtr Range, Make: Honey well @ children play area-2nos, three roads corners, Between Villas-6Nos, Main road-1No of Kanopy Lotus site.

1	CCTV Works	Supply and installation ,testing & commissioning of 2MP Our Door Bullet camera, Very focul type, 40Mtr Range, Make: Honey well @ children play area-2nos, three roads corners, Between Villas-6Nos, Main road-1No of Kanopy Lotus site. 1.Supply 2.Installation 3.T,C & Handing Over Supply and Installation of 8 channel DVR, Make: Honey well	NOS	9.00	5923.00	53307.00	J02.A.01.02
					80.00 %	42645.60	
					10.00 %	5330.70	
					10.00 %	5330.70	
2	CCTV Works	Supply and Installation of 8 channel DVR, Make: Honey well 1.Supply 2.Installation 3.T,C & Handing Over Supply and installation of BNC Connectors.	NOS	1.00	14000.00	14000.00	J02.A.01.03
					80.00 %	11200.00	
					10.00 %	1400.00	
					10.00 %	1400.00	
3	CCTV Works	Supply and installation of BNC Connectors. 1.Supply 2.Installation 3.T,C & Handing Over Supply and installation of Hard disk 4TB for 8 channel DVR & 4 Channel DVR, Make: Segate.(For 30days data back up)	NOS	18.00	50.00	900.00	J02.A.01.04
					80.00 %	720.00	
					10.00 %	90.00	
					10.00 %	90.00	
4	CCTV Works	Supply and installation of Hard disk 4 TB for 8 channel DVR & 4 Channel DVR, Make: Segate 1.Supply 2.Installation 3.T,C & Handing Over Supply and providing of 12V,5A,DC power supply Adaptor, Make:MX	NOS	2.00	11800.00	23600.00	J02.A.01.05
					80.00 %	18880.00	
					10.00 %	2360.00	
					10.00 %	2360.00	
5	CCTV Works	Supply and providing of 12V,5A,DC power supply Adaptor, Make:MX 1.Supply 2.Installation 3.T,C & Handing Over	NOS	4.00	750.00	3000.00	J02.A.01.06
					80.00 %	2400.00	
					10.00 %	300.00	
					10.00 %	300.00	

Signature

Ref. No : ASPL_CONS\J402-EXT.SER\S02172\ASP\SCO\402\0018\A0 (FRESH)

IBMS & Security

S/n	Work Area	Description of Work	UOM	Quantity	Rate	Amount	WBS ID
Supply & fixing of Router,Make:D-link							
6	CCTV Works	Supply & fixing of Router,Make:D-link	NOS	1.00	3548.00	3548.00	J02.A.01.07
		1.Supply			80.00 %	2838.40	
		2.Installation			10.00 %	354.80	
		3.T,C & Handing Over			10.00 %	354.80	
Supply & fixing of PVC 2 module back box with face plate for camera, make:Imported							
7	CCTV Works	Supply & fixing of PVC 2 module back box with face plate for camera, make: Imported	NOS	9.00	250.00	2250.00	J02.A.01.08
		1.Supply			80.00 %	1800.00	
		2.Installation			10.00 %	225.00	
		3.T,C & Handing Over			10.00 %	225.00	
Supply and fixing of video ballons set. make:MX							
8	CCTV Works	Supply and fixing of video ballons set, Make:MX	NOS	9.00	309.00	2781.00	J02.A.01.09
		1.Supply			80.00 %	2224.80	
		2.Installation			10.00 %	278.10	
		3.T,C & Handing Over			10.00 %	278.10	
Supply and installtion of 6U racks for DVR cables							
9	CCTV Works	Supply and installtion of 6U racks for DVR cables	NOS	3.00	4100.00	12300.00	J02.A.01.10
		1.Supply			80.00 %	9840.00	
		2.Installation			10.00 %	1230.00	
		3.T,C & Handing Over			10.00 %	1230.00	
Supply and installation of 32" LED moniters.Make: LG/MICROMAX/SAMSUNG							
10	CCTV Works	Supply and installation of 32" LED moniters.Make: LG/MICROMAX/SAMSUNG	NOS	1.00	32457.00	32457.00	J02.A.01.11
		1.Supply			80.00 %	25965.60	
		2.Installation			10.00 %	3245.70	
		3.T,C & Handing Over			10.00 %	3245.70	
Supply,laying,testing and commissioning of CAT6 cable,Make:Orbit/LAPP							
11	CCTV Works	Supply,laying,testing and commissioning of CAT6 cable,Make: Orbit/LAPP	RMT	600.00	26.00	15600.00	J02.A.01.12
		1.Supply			80.00 %	12480.00	
		2.Installation			10.00 %	1560.00	
		3.T,C & Handing Over			10.00 %	1560.00	
Supply and Laying Of 2 core 1.5 sqmm Power Cable,Make:POLYCAB/RR/KEI.							
12	CCTV Works	Supply and Laying Of 2 core 1.5 sqmm Power Cable,Make:POLYCAB/RR/KEI	RMT	600.00	40.00	24000.00	J02.A.01.13
		1.Supply			80.00 %	19200.00	
		2.Installation			10.00 %	2400.00	
		3.T,C & Handing Over			10.00 %	2400.00	

34

Ref. No : ASPL_CONS\402-EXT.SER\S02172\ASPI\SCO\402\0018\A0 (FRESH)

IBMS & Security

S/n	Work Area	Description of Work	UOM	Quantity	Rate	Amount	WBS ID
Supply and laying of following size PVC conduits of 25mm dia 1.6mm thick to run on surface of wall/ above false ceiling with all fixing accessories/ materials for Access Control System Works.make: Sudhakar							
13	CCTV Works	Supply and laying of following size PVC conduits of 25mm dia 1.6mm thick to run on surface of wall/ above false ceiling with all fixing accessories/ materials for Access Control System Works.make: Sudhakar	RMT	600.00	45.00	27000.00	J02.A.01.14
		1.Supply			80.00 %	21600.00	
		2.Installation			10.00 %	2700.00	
		3.T,C & Handing Over			10.00 %	2700.00	
Supply and Installation Of 1 KVA ups for 2 hours backup,Make: INTEX/ZEBRONIX							
14	CCTV Works	Supply and Installation Of 1 KVA ups for 2 hours backup,Make: INTEX/ZEBRONIX	NOS	3.00	5723.00	17169.00	J02.A.01.15
		1.Supply			80.00 %	13735.20	
		2.Installation			10.00 %	1716.90	
		3.T,C & Handing Over			10.00 %	1716.90	
Supply & Laying of 3D supported ,HDMI cable,make:Imported							
15	CCTV Works	Supply & Laying of 3D supported ,HDMI cable,make:Imported	RMT	5.00	1633.00	8165.00	J02.A.01.16
		1.Supply			80.00 %	6532.00	
		2.Installation			10.00 %	816.50	
		3.T,C & Handing Over			10.00 %	816.50	
Supply and Installation of 4 channel DVR,Make:Honeywell.							
16	CCTV Works	Supply and Installation of 4 channel DVR,Make:Honeywell	NOS	1.00	10800.00	10800.00	J02.A.01.18
		1.Supply			80.00 %	8640.00	
		2.Installation			10.00 %	1080.00	
		3.T,C & Handing Over			10.00 %	1080.00	
Supply & fixing of 6 core OFC cable, Make:Digisol/D-link							
17	CCTV Works	Supply & fixing of 6 core OFC cable, Make:Digisol/D-link	RMT	200.00	39.00	7800.00	J02.A.01.19
		1.Supply			80.00 %	6240.00	
		2.Installation			10.00 %	780.00	
		3.T,C & Handing Over			10.00 %	780.00	
CCTV data networking							
18	CCTV Works	Supply and fixing of 4 PORT POE SWITCH,Make: Digisol	NOS	1.00	10800.00	10800.00	J02.A.01.20
		1.Supply			80.00 %	8640.00	
		2.Installation			10.00 %	1080.00	
		3.T,C & Handing Over			10.00 %	1080.00	
19	CCTV Works	Supply & fixing of Media converter power rack,Make: Digisol	NOS	4.00	4100.00	16400.00	J02.A.01.21
		1.Supply			80.00 %	13120.00	
		2.Installation			10.00 %	1640.00	
		3.T,C & Handing Over			10.00 %	1640.00	
20	CCTV Works	Installation charges for Spiling of fiber	RMT	16.00	500.00	8000.00	J02.A.01.22
		1.Supply			80.00 %	6400.00	
		2.Installation			10.00 %	800.00	
		3.T,C & Handing Over			10.00 %	800.00	

24/11/2018

4 of 5

Ref. No : ASPL_CONSJ402-EXT.SER\502172\ASP\SCO\402\0018\A0 (FRESH)

IBMS & Security

S/n	Work Area	Description of Work	UOM	Quantity	Rate	Amount	WBS ID
-----	-----------	---------------------	-----	----------	------	--------	--------

Grand Total

293877.00

Amount in words Rupees Two Lakh Ninety Three Thousands Eight Hundred Seventy Seven Only

Trishu
Syl

Clap

ANNEXURE – II

This Annexure-2 forms an integral part of ASPL\WO\402\0018\AO, Dt: 23.11.2018

Scope of work

Your scope of work includes

1. Supply and installation of 2 mega pixel IR WR Bullet Camera wide range of 40mtr , Make: Honeywell ,Qty: 9Nos(Location details mentioned in Annexure-3)
2. Supply and installation of 8 channel DVR(Make: Honeywell Qty:1Nos) & 4 channel DVR-1No with 4TB Hard disk (Qty:01 No ,Make: Segate/western digital) for 30 days storage with IP connectivity.
3. Scope also includes Supply and laying of RG 6 cable for video streaming data.
4. Supply & Laying of 25mm PVC conduit 25mm with all accessories is to your Scope
5. Locations of cameras are mentioned in enclosed Annexure-III. In case any deviations prior Approvals should be taken from Project in charge.

Makes of Material used in the system shall be conforming to Indian Standards wherever applicable and tender document. In case any deviations, prior approval must be taken from DGM-MEP/ Site in-charge.

Any Statutory related agreement/approvals to be taken care by you, all unspecified parameters shall be as per tender document given by us.

Price: Details as per Annexure-I enclosed

Payment terms :

80% payment shall be made against supply of material against running bills certified by our project in charge.

10% after erection, 10% after commissioning and handing over.

Taxes :

Taxes shall be paid extra as / if applicable.

Schedule:

As per site requirement.



Warranty :

You shall provide warranty of 24 months from the date of Handing over

Water & Electricity:

We shall provide you water & Electricity at one point.

Insurance & Others:

You shall provide at your cost insurance coverage for all the workers, labour, workmen's compensation policy and third party liability.

You shall be wholly responsible for full compliance with the provisions under all labour.

You shall not employ any labour less than 18 Years of age on the job.

You will be responsible and liable for payment for all personnel employed by you and statutory liability like PF, ESI Payments under workmen compensation act.

You must provide us proof of compliances of above; in the event of non-compliance of above we shall deduct the same from your bills and pay to the concern statutory authorities.

You shall comply with safety precautions, protective measures, house keeping requirements etc.

You are held responsible for non compliances if any injuries, fatalities and compensation arising out of such incidents.

You shall cooperate with all other agencies at this site to ensure smooth execution of the project.



ANNEXURE – III

This Annexure-3 forms an integral part of ASPL\WO\402\0018\AO, Dt: 23.11.2018

SNO	LOCATION	UNIT	QTY	CAMERA TYPE
1	Children play area	Nos	2	Bullet
2	Main Road	Nos	1	Bullet
3	Three Road Corners between Villas	Nos	6	Bullet

Sy

Q/100